



THE SSC CONTROLS COMPANY

THE FOOT SWITCH EXPERTS®

Product Information Sheet

F-Series Medium-Duty Foot Switch

Designed for a wide variety of applications, the F-Series Foot Switch features a tough die-cast zinc housing, attractive shape, easy wire hookup, and numerous switch / cable combinations.

Design features:

- Die-cast housing provides superior appearance and durability.
- Durable zinc alloy will not rust or easily break.
- Powder-painted black with bottom traction pad.
- Cable cord grip fits up to .60" cable diameter.
- Includes two exterior mounting holes for bolt-down option.
- Model F300 can be used to control lighting (push on / push off) and many other maintained-action applications.



Quality features:

- Quality system certified to ISO 9001 requirements.
- Includes a 1-year warranty on parts and labor.
- Made in USA of imported and domestic components.



Model F200-1501 shown on left and F200-1502 on right.

Dimensions (L x W x H): 4.8" x 3.5" x 1.8"

Weight: 2.1 pounds (without cable)

Finish: powder paint

Enclosure rating: CSA Type 1; IEC IP-21



Warning: To avoid personal injury, do not use foot switches on machinery lacking effective point-of-operation safeguards. Disconnect input power before installation or maintenance.

| Model | Action | Switches | Electrical Rating, per Switch* | Cable |
|-----------|--------------------|----------|--|----------------------------|
| F200 | Momentary | 1 | 15 A, ½ HP, 125/250 VAC | none |
| F200-1501 | Momentary | 1 | 15 A, ½ HP, 125 VAC | cable with plug for outlet |
| F200-1502 | Momentary | 1 | 15 A, ½ HP, 125/250 VAC | cable with leads |
| F202 | Momentary | 2 | 15 A, ½ HP, 125/250 VAC; DPDT | none |
| F222 | Momentary, 2-Stage | 2 | 15 A, 125/250 VAC; each stage SPDT | none |
| F300 | Maintained | 1 | 20 A, 125 VAC; 10 A, 250 VAC | none |
| F300-1501 | Maintained | 1 | 15 A, 125 VAC | cable with plug for outlet |
| F300-1502 | Maintained | 1 | 15 A, 125/250 VAC | cable with leads |
| F500 | Momentary | 1 | 20A, 125/250 VAC; 1 HP, 125 VAC; 2 HP, 250 VAC | none |
| F500-1501 | Momentary | 1 | 15 A, ¾ HP, 125 VAC | cable with plug for outlet |
| F502 | Momentary | 1 | 10 A, 125/250 VAC (DPDT) | none |
| F540 | Momentary | 1 | 15 A, 125 VAC; 1 A, 125 VDC (SPDT-DB) | none |

*All switches have SPDT circuits except as noted. Units with cables are wired Normally Open (N.O.).

The SSC Controls Company
 8909 East Avenue Mentor, Ohio 44060
 Phone: 440 205-1600 Fax: 440 205-1700